

VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION

TABLE OF CONTENTS

TABLE OF CONTENTS	i
--------------------------------	----------

EXECUTIVE SUMMARY	E-1
Introduction	E-1
Summary of the Regulatory Approval Process	E-1
Need (Section 1)	E-3
Protection of the Public Health, Welfare, and Safety (Section 2)	E-4
Location (Section 2.1)	E-4
Hydrogeology (Section 2.2)	E-4
Engineered Design (Section 2.3)	E-4
Composite Liner	E-5
Leachate Collection	E-5
Final Cover	E-5
Landfill Gas Generation	E-5
Stormwater Management (Section 2.4)	E-6
Construction Quality Assurance Program (Section 2.5)	E-6
Operating Plan (Section 2.6)	E-6
Groundwater Impact Evaluation (Section 2.7)	E-7
Groundwater Monitoring (Section 2.8)	E-7
Closure and Post-Closure Care Plan (Section 2.9)	E-7
Development and Review of Design	E-7
Section 2 Summary	E-8
Land Use / Real Estate (Section 3)	E-9
Floodplains (Section 4)	E-9
Fire/Spill/Accident Prevention (Section 5)	E-10
Traffic (Section 6)	E-10
Hazardous Waste Ban (Section 7)	E-10
Solid Waste Management Plan consistency (Section 8)	E-10
Regulated Recharge Areas (Section 9)	E-11
Operating Experience of Applicant (Section 10)	E-11
Conclusion	E-11

CITY OF ZION POLLUTION CONTROL FACILITY SITING ORDINANCE	
REQUIREMENT SUMMARY TABLE	SITING ORDINANCE SUMMARY TABLE

SECTION 1.0 - NEED

Purpose	1.0-1
Proposed Service Area	1.0-2
Size of Expansion	1.0-4
Types of Waste Received	1.0-4
Data Sources	1.0-4
Waste Management in the Service Area	1.0-6
History of Waste Management in Lake County	1.0-6
History of Waste Management in Other Counties in the Service Area	1.0-8
Future Management of Waste in the Service Area	1.0-12
Waste Disposal in the Service Area	1.0-15
Service Area Disposal Quantities	1.0-15



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION

TABLE OF CONTENTS

Service Area Disposal Capacity	1.0-18
Service Area Disposal Capacity	1.0-18
Regional Capacity Considerations	1.0-20
Economic Considerations	1.0-24
Potential Additions to Capacity	1.0-28
Other Factors Underlying Need	1.0-30
Conclusions	1.0-31
References	1.0-33

SECTION 2.0 - HEALTH, SAFETY, AND WELFARE

Introduction	2.0-1
--------------------	-------

SECTION 2.1 - LOCATION

Introduction	2.1-1
Project Location	2.1-1
Site History	2.1-1
Proposed Facility Overview	2.1-2
Legal Description	2.1-2
Site Location Standards	2.1-2

SECTION 2.2 - HYDROGEOLOGIC INVESTIGATION

Hydrogeologic Investigation	2.2-1
Objectives of the Investigation	2.2-2
Project Background	2.2-3
Proposed Location	2.2-3
Site History	2.2-3
Climate Data	2.2-6
Regional Geology and Hydrogeology	2.2-7
Methodology	2.2-7
Water Wells	2.2-7
Topography and Relief	2.2-8
Surficial Soils	2.2-8
Regional Bedrock Stratigraphy	2.2-8
Regional Bedrock Topography	2.2-21
Regional Bedrock Structural Features	2.2-21
Seismic Risk	2.2-21
Unconsolidated Deposits	2.2-24
Regional Groundwater Resources	2.2-29
Bedrock Groundwater Resources	2.2-31
Surficial and Glacial Deposit Groundwater Resources	2.2-31
Aquifer Sensitivity	2.2-32
Site Specific Hydrogeologic Investigation	2.2-32
Recent Hydrogeologic Investigation Methodology	2.2-37
Drilling and Field Procedures	2.2-37



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION TABLE OF CONTENTS

Soil Sampling	2.2-37
Piezometer and Monitoring Well Installation	2.2-38
Piezometer and Monitoring Well Development	2.2-39
Surveying	2.2-39
Borehole Abandonment Procedures	2.2-40
Water Level Measurements	2.2-40
In-Situ Hydraulic Conductivity Testing	2.2-40
Laboratory Soil Testing	2.2-41
Site Geology	2.2-43
Bedrock	2.2-43
Unconsolidated Deposits	2.2-43
Peoria Silt	2.2-43
Wadsworth Formation	2.2-44
Shallow Drift	2.2-46
Lower Till	2.2-46
Basal Drift	2.2-46
Site Hydrogeology	2.2-47
Uppermost Aquifer	2.2-48
Geologic and Hydrogeologic Conclusions	2.2-49
Hydrogeologic References	2.2-51

SECTION 2.3 - DESIGN

Introduction	2.3-1
Landfill History	2.3-2
Design Period	2.3-2
Landfill Composite Liner System	2.3-3
Effectiveness of Landfill Composite Liner Systems	2.3-3
Hydrogeology Considerations	2.3-3
Recompacted Soil Liner	2.3-4
Geomembrane	2.3-4
CQA Documentation	2.3-5
Geotechnical Analyses	2.3-5
Slope Stability	2.3-6
Seismic Analysis	2.3-6
Failure Scenarios	2.3-6
Bearing Capacity Analysis	2.3-8
Landfill Settlement	2.3-8
Foundation Settlement	2.3-8
Waste Compression	2.3-9
Anchor Trench/Runout Design	2.3-10
Leachate Management	2.3-10
Origin of Leachate	2.3-10
Leachate Collection System	2.3-11
Leachate Collection System Efficiency (Ability to Remove Leachate from the Landfill)	2.3-13
Leachate Collection and Disposal	2.3-13
Leachate Storage Tank and Secondary Containment System	2.3-14



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION TABLE OF CONTENTS

Leachate Treatment	2.3-14
Automatic Extraction and Recirculation System Operations	2.3-14
Leachate Monitoring	2.3-15
Construction Phasing	2.3-15
Initial Filling Sequence	2.3-16
Material Balance	2.3-16
Borrow Areas	2.3-16
Soil Stockpiling	2.3-18
Final Cover System	2.3-18
Low Permeability Layer	2.3-18
Geomembrane Layer	2.3-18
Geocomposite	2.3-18
Protective Layer	2.3-19
Vegetation	2.3-19
Final Cover Construction and Maintenance	2.3-19
Cover Percolation	2.3-19
Final Landform	2.3-20
Landfill Gas Management	2.3-20
Landfill Gas Composition	2.3-20
Quantity of Landfill Gas	2.3-21
Landfill Gas Monitoring	2.3-22
Waste Unit Monitoring	2.3-22
Below Ground Perimeter Monitoring	2.3-23
Ambient Air Monitoring	2.3-23
Continuous Air Monitoring Within Buildings	2.3-23
Landfill Gas Collection	2.3-23

SECTION 2.4 - STORMWATER MANAGEMENT PLAN

Introduction	2.4-1
Stormwater Requirements	2.4-2
Physiography and Topography	2.4-4
Soil Conditions	2.4-4
Climate	2.4-5
Precipitation Data	2.4-5
FEMA Regulatory 100-Year Floodplain Limits	2.4-5
Isolated Waters of Lake County	2.4-5
Depressional Survey	2.4-6
Field Tile Survey	2.4-6
Developed Site Conditions	2.4-6
Terrace Berms and Benches	2.4-6
Downslope Flume Pipes	2.4-8
Energy Dissipators	2.4-9
Perimeter Ditches and Culverts	2.4-9
Detention Basins	2.4-11
Staged Outlet Structures	2.4-11
Bioswale	2.4-12
Runoff Volume Reduction Hierarchy	2.4-12



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION

TABLE OF CONTENTS

Hydrologic Analysis	2.4-13
Hydrologic Results	2.4-14
Review of Release Rates to Regional Watersheds	2.4-21
Comparison of Existing to Proposed Release Rates	2.4-22
Stormwater Controls During Cell Development	2.4-23
NPDES Requirements	2.4-23
Final Grading	2.4-23
Vegetative Soil Stabilization	2.4-24
Non-Vegetative Soil Stabilization	2.4-24
Erosion and Sediment Control	2.4-24
Sedimentation Basin Design	2.4-25
Inspection and Maintenance	2.4-25
Conclusion	2.4-25

SECTION 2.5 - CONSTRUCTION QUALITY ASSURANCE PLAN

Table of Contents	2.5.1-i
Purpose and Scope	2.5.1-1
Purpose	2.5.1-1
Scope	2.5.1-1
Operator and CQA Roles, Responsibilities, and Qualification	2.5.2-1
Owner/Operator	2.5.2-1
CQA Officer	2.5.2-1
Resident Project Representative (RPR)	2.5.2-1
CQA Officer-In-Absentia	2.5.2-2
Soils Testing Laboratory	2.5.2-2
Geosynthetic Testing Laboratory	2.5.2-2
Preconstruction Meeting	2.5.3-1
General Construction Observation and Documentation	2.5.4-1
Daily Reports	2.5.4-1
Forms, Checklists, and Data Sheets	2.5.4-2
Problem/Deficiency Identification and Corrective Action	2.5.4-2
Photographic Documentation	2.5.4-2
Surveying	2.5.4-3
Construction Acceptance Report	2.5.5-1
Narrative	2.5.5-1
Photographic Documentation	2.5.5-1
Summary Reports	2.5.5-1
Drawings of Record	2.5.5-1
Subgrade and Foundation	2.5.6-1
Procedures and Observation	2.5.6-1
Excavation	2.5.6-1
Sampling Requirements and Acceptance Criteria	2.5.6-2
Surveying	2.5.6-1
Test Liner	2.5.7-1
Test Liner Design	2.5.7-1
Procedures and Observation	2.5.7-1



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION **TABLE OF CONTENTS**

Sampling Requirements and Acceptance Criteria	2.5.7-2
Surveying	2.5.7-3
Low-Permeability Soils	2.5.8-1
Procedures and Observation	2.5.8-1
Sampling Requirements and Acceptance Criteria	2.5.8-2
Surveying	2.5.8-4
General Soils	2.5.9-1
Procedures and Observation	2.5.9-1
Sampling Requirements and Acceptance Criteria	2.5.9-1
Surveying	2.5.9-2
Granular Soils	2.5.10-1
Procedures and Observation	2.5.10-1
Sampling Requirements and Acceptance Criteria	2.5.10-1
Surveying/Thickness Determination	2.5.10-2
Geomembranes	2.5.11-1
Pre-Installation	2.5.11-1
Installation	2.5.11-3
Defects and Repairs	2.5.11-7
Field Seaming	2.5.11-8
Post-Construction	2.5.11-18
Leak Location Survey	2.5.11-19
Geotextiles	2.5.12-1
Pre-Installation	2.5.12-1
Installation	2.5.12-3
Post-Installation	2.5.12-4
Geonets	2.5.13-1
Pre-Installation	2.5.13-1
Installation	2.5.13-2
Post-Installation	2.5.13-4
Geocomposites	2.5.14-1
Pre-Installation	2.5.14-1
Installation	2.5.14-2
Post-Installation	2.5.14-3
Piping	2.5.15-1
Pre-Installation	2.5.15-1
Installation	2.5.15-2
Post-Installation	2.5.15-3
Surface Water Control Facilities	2.5.16-1
Procedures and Observation	2.5.16-1
Surveying and Acceptance Criteria	2.5.16-1
Deviations	2.5.16-2
Gas Extraction Wells	2.5.17-1
Installation of Gas Extraction Wells	2.5.17-1
Seeding, Fertilizing, and Mulching	2.5.18-1
Leachate Storage Tanks	2.5.19-1
Tables	2.5.20-1
Forms	2.5.21-1



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION

TABLE OF CONTENTS

SECTION 2.6 - OPERATING PLAN

Introduction	2.6-1
Personnel Requirements and Training	2.6-1
General Manager	2.6-2
Operations Manager	2.6-2
Scalehouse Attendant	2.6-2
Equipment Operators	2.6-2
Laborers	2.6-3
Landfill Administrators	2.6-3
Equipment	2.6-3
Utilities	2.6-3
Operation Controls	2.6-4
Operating Hours	2.6-4
Operating Life	2.6-4
Cell Development	2.6-4
Access Controls	2.6-5
Litter Control	2.6-5
Mud Tracking	2.6-5
Air Quality Plan	2.6-6
Dust Control	2.6-6
Noise Control	2.6-6
Odor Control	2.6-6
Vector Control	2.6-7
Open Burning	2.6-7
Salvaging	2.6-7
Transportation Plan	2.6-7
Waste Acceptance Procedures	2.6-7
Type of Waste Accepted	2.6-8
Weighing and Control of Waste Volumes	2.6-9
Record Keeping	2.6-9
Nonhazardous Special Wastes	2.6-10
Facility Sign	2.6-10
Profile Identification Record	2.6-10
Special Waste Manifests	2.6-11
Waste Analysis Plan	2.6-12
Acceptance Criteria	2.6-13
Special Waste Record Keeping	2.6-14
Declassification of Special Waste	2.6-14
Load Checking Program	2.6-15
Customer Education	2.6-15
Employee Training	2.6-16
Regular Checkpoints	2.6-16
Random Inspections	2.6-16
Special Waste Load Checks	2.6-16
Record Keeping	2.6-17
Handling of Unauthorized Wastes	2.6-17



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION TABLE OF CONTENTS

Temporary Waste Storage	2.6-18
Survey Controls	2.6-18
Waste Placement and Compaction	2.6-18
Size and Slope of the Active Fill Area	2.6-19
Cover Materials and Placement	2.6-19
Daily Cover	2.6-19
Intermediate Cover	2.6-20
Final Cover	2.6-21
Maintenance Program	2.6-21
Equipment	2.6-21
Leachate Systems	2.6-21
Monitoring Systems	2.6-21
Cover Systems	2.6-21
Drainage/Erosion Control Systems	2.6-22
Access Controls	2.6-22
Roads	2.6-22
Leachate Management and Monitoring Procedures	2.6-22
Operation of the Leachate Collection and Recirculation System	2.6-22
Automatic Extraction and Recirculation System Operations	2.6-23
Response Plan to Potential Leachate Runoff	2.6-23
Leachate Disposal	2.6-23
Leachate Monitoring	2.6-24
Landfill Gas Management and Monitoring Procedures	2.6-24
Landfill Gas Collection	2.6-24
Landfill Gas Monitoring	2.6-24
Groundwater Monitoring	2.6-25
Stormwater and Erosion Control	2.6-25
Health and Safety Policies	2.6-25

SECTION 2.7 - GROUNDWATER IMPACT EVALUATION

Introduction	2.7-1
Summary of Findings	2.7-2
Proposed Landfill Evaluations	2.7-2
Groundwater Impact Evaluation Approach	2.7-2
Landfill Design Considerations	2.7-3
Leachate Quality Characterization and Groundwater Quality Standards	2.7-3
Leachate Quality Characterization	2.7-3
Groundwater Quality Standards	2.7-4
Groundwater Impact Evaluation Model	2.7-4
Conversion of Conceptual Model to Mathematical Model	2.7-4
Calculating Predicted Groundwater Concentrations	2.7-6
Interpretation of POLLUTE Model Results	2.7-6
GIE Model Input	2.7-7
Model Input	2.7-7
Model Length	2.7-7
Initial Leachate Concentration	2.7-7
Number of Layers	2.7-7



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION TABLE OF CONTENTS

Modeling Period	2.7-10
Talbot Parameters	2.7-10
Boundary Conditions	2.7-10
Advective (Darcy) Velocity	2.7-10
Hydrodynamic Dispersion Coefficient	2.7-10
Porosity and Dry Density Input	2.7-11
Adsorption Coefficient	2.7-11
Degradation	2.7-11
Model Evaluation Distance	2.7-11
Model Results	2.7-12
Anticipated Site Conditions Phase	2.7-12
Sensitivity Analysis	2.7-12
Coefficient of Hydrodynamic Dispersion	2.7-12
Porosity	2.7-18
Layer Thickness	2.7-18
Darcy Velocity	2.7-18
Model Reliability	2.7-19
Conservativeness of Baseline Model	2.7-19
GIE Conclusions	2.7-19
References	2.7-20

SECTION 2.8 - ENVIRONMENTAL MONITORING

Introduction	2.8-1
Groundwater Monitoring	2.8-1
Groundwater Monitoring Overview	2.8-1
Proposed Groundwater Monitoring Network	2.8-1
Monitoring Well Spacing Determination	2.8-9
MEMO Input Data	2.8-10
Coordinate Data	2.8-10
Hydrogeological Data	2.8-10
Monitoring Well Phasing	2.8-13
Establishment of Applicable Groundwater Quality Standards	2.8-13
Outlier Testing of Background Groundwater Quality Data	2.8-14
Statistical Evaluation of Background Groundwater Quality Data	2.8-14
Maximum Allowed Predicted Concentrations (MAPCs)	2.8-14
Design and Construction of Monitoring Wells	2.8-14
Monitoring Well and Boring, Pulgging and Abandonment	2.8-16
Test Boring Abandonment	2.8-16
Monitoring Well or Piezometer Abandonment	2.8-16
Groundwater Sampling Procedures	2.8-17
Detection Monitoring Parameters, Frequency and Data Analyses	2.8-17
Monitoring Prior to Accepting Waste	2.8-17
Detection Monitoring During Landfill Operation	2.8-18
Monitoring During Post-Closure	2.8-18
Statistical Analysis of Groundwater Quality Data	2.8-18
Evaluation of Groundwater Quality Data	2.8-18
Confirmation of Observed Increase	2.8-19

VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION

TABLE OF CONTENTS

Leachate Monitoring	2.8-19
Leachate Monitoring Overview	2.8-19
Leachate Monitoring Points	2.8-20
Subsurface Landfill Gas Monitoring	2.8-20
Ambient Air Monitoring	2.8-22
Surface Water Monitoring	2.8-22
Conclusions	2.8-22

SECTION 2.9 - CLOSURE AND POST-CLOSURE CARE PLAN

Introduction	2.9-1
Closure Requirements	2.9-2
Premature Closure	2.9-3
Equipment Decontamination	2.9-3
Site Security	2.9-3
Stormwater Management	2.9-3
Final Cover Placement	2.9-5
Structures Constructed Over the Unit	2.9-6
Landfill Gas Monitoring	2.9-6
Groundwater Monitoring	2.9-6
Certification of Closure	2.9-6
Documentation	2.9-6
Schedule of Premature Closure	2.6-6
Temporary Suspension of Operations	2.9-8
Routine Closure	2.9-9
Stormwater Management	2.9-9
Final Cover Placement	2.9-9
Certification of Closure	2.9-9
Post-Closure Care Requirements	2.9-11
Maintenance and Inspection	2.9-11
Final Cover	2.9-11
Vegetation	2.9-11
Drainage Control	2.9-12
Landfill Gas Monitoring and Collection	2.9-12
Groundwater Monitoring	2.9-12
Leachate Management	2.9-12
Record Keeping	2.9-13
Security	2.9-13
Cost Estimates	2.9-13
Financial Assurance	2.9-13



**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

**SECTION 3.0 - MINIMIZE INCOMPATIBILITY AND EFFECT ON VALUE OF THE
SURROUNDING PROPERTY**

Introduction	3.0-1
--------------------	-------

SECTION 3.1 - LAND USE AND PLANNING ANALYSIS

Table of Contents	3.1-2
Executive Summary	3.1-3
Introduction and Methodology	3.1-4
Facility Location and Nature of Proposed Activity	3.1-4
Surrounding Land Use	3.1-6
Existing Land Use Inventory	3.1-7
Off-Site Views	3.1-8
Findings	3.1-10
Zoning	3.1-11
Facility Zoning	3.1-11
Zoning Adjacent to the Facility	3.1-11
Findings	3.1-13
Master Comprehensive Plan	3.1-13
Landscape Plan/Conceptual End Use Plan	3.1-13
Computer Models	3.1-14
Findings	3.1-15
Conclusion	3.1-16
References	3.1-17

SECTION 3.2 - REAL ESTATE IMPACT STUDY

Table of Contents	3.2-2
General Information	3.2-3
Introduction	3.2-3
Facility Location & Surrounding Uses	3.2-4
Facility Description of the Proposed Improvements	3.2-8
Trends	3.2-10
Measuring Impact	3.2-14
Conclusions	3.2-19
Certificate - Evaluation Report	3.2-20
Appendix 1 - Qualifications of Appraisers	3.2 - Appendix I

SECTION 4.0 - FLOODPLAIN ASSESSMENT

Regulatory Requirements	4.0-1
Facility Location	4.0-1



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION TABLE OF CONTENTS

SECTION 5.0 - PLAN OF OPERATIONS IS DESIGNED TO MINIMIZE DANGER TO SURROUNDING AREA FROM FIRE, SPILLS, OR OTHER OPERATIONAL ACCIDENTS

Overview	5.0-1
Site Safety Procedures	5.0-1
Safety Training	5.0-1
Machinery Safety	5.0-2
Personal Protective Equipment	5.0-2
Confined Space Entry	5.0-2
Lockout/Tagout Program	5.0-2
Vandalism	5.0-2
Materials Handling and Use	5.0-2
Spill Prevention and Control	5.0-3
Load Checking Program	5.0-3
Fire Prevention	5.0-4
General Landfill Development Procedures	5.0-4
Site Construction	5.0-4
Site Operations	5.0-5
Post-Closure	5.0-5
Emergency Preparedness Program	5.0-5
Emergency Response	5.0-6
Medical Services and First-Aid	5.0-6
Fires	5.0-6
Explosions	5.0-6
Severe Weather	5.0-6
Chemical and Hazardous Waste Spill	5.0-6
Terrorist Attacks	5.0-7
Bloodborne Pathogen Exposure	5.0-7
Conclusion	5.0-7

SECTION 6.0 - TRAFFIC IMPACT ANALYSIS

Introduction	6.0-i
Table of Contents	6.1-ii
List of Figures and Tables	6.1-iii
Introduction	6.1-1
Methodology	6.1-2
Site Accessibility Investigation and Data Collection	6.1-2
Traffic Characteristics of the Proposed Project	6.1-2
Traffic Assignment and Analysis	6.1-3
Roadway and Site Access Requirements	6.1-3
Site Accessibility	6.1-4
Site Location	6.1-4
Study Area	6.1-5
Area Roadways	6.1-6
Proposed Roadway Improvements	6.1-8
March 2008 Existing Traffic Volumes	6.1-8



**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

Development Traffic Characteristics	6.1-11
Truck Traffic Dimensions	6.1-11
Directional Distribution	6.1-12
Estimated Site Traffic Generation	6.1-14
Future Growth	6.1-15
Traffic Assignments	6.1-17
Traffic Impact Analysis	6.1-22
Intersection Capacity Analyses	6.1-22
Accident Data	6.1-26
Site Access	6.1-27
Gap Study	6.1-28
Conclusion	6.1-32

SECTION 7.0 - HAZARDOUS WASTE PRECLUSION

Regulatory Requirements	7.0-1
Waste Screening Process/Emergency Response Plan	7.0-1

SECTION 8.0 - PLAN CONSISTENCY

Introduction	8.0-1
Summary of the Planning Process and the Plan	8.0-1
The 1989 Solid Waste Management Plan	8.0-1
Five-Year Plan Update (1994 Plan Update)	8.0-2
Ten-Year Plan Update (1999 Plan Update)	8.0-3
Fifteen-Year Plan Update (2004 Plan Update)	8.0-4
Summary of Plan Development	8.0-5
Consistency with the Plan	8.0-7
Conclusion	8.0-9
References	8.0-10

SECTION 9.0 - REGULATED RECHARGE AREA

Regulatory Requirements	9.0-1
Summary of Findings	9.0-1

SECTION 10.0 - PREVIOUS OPERATING EXPERIENCE

Introduction	10.0-1
--------------------	--------



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION

TABLE OF CONTENTS

FIGURES

SECTION 1.0

1.0-1 Proposed Service Area	1.0-3
1.0-2 Landfill Closures in Service Area	1.0-10
1.0-3 Reported Municipal Solid Waste Diversion Rates	1.0-14
1.0-4 Historical Trends in Waste Disposal Quantities	1.0-17
1.0-5 Number of Landfills in Service Area	1.0-19
1.0-6 Disposal Facilities Included in Capacity Analysis	1.0-21
1.0-7 Disposal Capacity Versus Distance from Lake County	1.0-25
1.0-8 Disposal Capacity Versus Distance from Service Area	1.0-26
1.0-9 Midwest Diesel Fuel Prices	1.0-27

SECTION 2.1

2.1-1 Proposed Facility Location	2.1-3
--	-------

SECTION 2.2

2.2-1 Regional Site Location Map	2.2-4
2.2-2 Site Location Map	2.2-5
2.2-3 Physiographic Divisions of Illinois	2.2-9
2.2-4 General Soil Map for the Vicinity of the Proposed Expansion	2.2-10
2.2-5 Generalized Stratigraphic Column in the Vicinity of the Proposed Expansion .	2.2-11
2.2-6 Top Elevation fo the Mt. Simon Sandstone	2.2-12
2.2-7 Elevation and Thickness of the Eau Claire Formation in Lake County	2.2-14
2.2-8 Elevation and Thickness of the Ironton-Galesville Formation in Lake County .	2.2-15
2.2-9 Elevation of Ancell Formation and Thickness of the Ancell, Franconia, Potosi, and Eminence Units in Lake County	2.2-17
2.2-10 Elevation and Thickness of the Galena-Platteville Dolomite in Lake County .	2.2-18
2.2-11 Elevation and Thickness of the Maquoketa Formation in Lake County	2.2-19
2.2-12 Bedrock Topography and Thickness of the Silurian Dolomite in Lake County	2.2-20
2.2-13 Bedrock Topography of Illinois	2.2-22
2.2-14 Structural Features in Illinois	2.2-23
2.2-15 Map of Horizontal Acceleration	2.2-25
2.2-16 Quaternary Deposits of Illinois	2.2-26
2.2-17 Surficial Deposits in the Vicinity of the Site	2.2-27
2.2-18 Regional Cross Section	2.2-28
2.2-19 Moraines in Lake County	2.2-30
2.2-20 Surficial Materials of Lake County Differentiated on Basis of Properties Related to Waste Disposal	2.2-33
2.2-21 Potential for Contamination of Shallow Aquifers from Land Burial of Municipal Wastes	2.2-34

SECTION 2.3

2.3-1 Site Phasing Plan	2.3-17
-------------------------------	--------

SECTION 2.4

2.4-1 Watershed Delineation	2.4-15
-----------------------------------	--------



**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

SECTION 2.5

Officer-In-Absentia	2.5.21-2
---------------------------	----------

SECTION 2.7

2.7-1 Groundwater Impact Evaluation/ Conceptual Model	2.7-5
---	-------

SECTION 2.8

2.8-1 Existing Monitoring Well Network	2.8-7
2.8-2 Proposed Monitoring Well Network	2.8-8
2.8-3 Longitudinal Dispersivity Flow Path Distance	2.8-12
2.8-4 Proposed Leachate Monitoring Network	2.8-21

SECTION 2.9

2.9-1 Premature Closure	2.9-4
2.9-2 Routine Closure	2.9-10

SECTION 3.1

3.1-1 Facility Location Map	3.1-5
3.1-2 Land Use Aerial	3.1-18
3.1-3 Off Site Views	3.1-19
3.1-4 Off Site Views	3.1-20
3.1-5 Off Site Views	3.1-21
3.1-6 Zoning Aerial	3.1-22
3.1-7 Preliminary Landscape Plan	3.1-23
3.1-8 Landscape Enlargements	3.1-24
3.1-9 Cross Sections	3.1-25
3.1-10 3-D Views	3.1-26
3.1-11 3-D Views	3.1-27
3.1-12 3-D Views	3.1-28

SECTION 3.2

3.2-1 Veolia ES Land Use Aerial (Lannert)	3.2-5
3.2-2 Existing Subdivision Map	3.2-13
3.2-3a Zion Market Analysis Chart	3.2-16
3.2-3b Winthrop Harbor Market Analysis Chart	3.2-16

SECTION 6.1

6.1-1 Site Location	6.1-7
6.1-2 March 2008 Existing Peak Hour Volumes	6.1-9
6.1-3 Directional Distribution	6.1-13
6.1-4 Expansion-Generated Peak Hour Volumes	6.1-18
6.1-5 Year 2012 Projected Peak Hour Volumes Without the Expansion- Generated Traffic	6.1-19
6.1-6 Year 2012 Projected Peak Hour Volumes With the Expansion- Generated Traffic	6.1-20



**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

TABLES

SECTION 1.0

1.0-1 Status of Publicly-Owned Disposal Facilities in Service	1.0-8
1.0-2 Historical Management of Waste in Service America (1988-1992)	1.0-11
1.0-3 Summary of Current and Goal Recycling Rates	1.0-12
1.0-4 Historical Trends in Waste Disposal Quantities	1.0-16

SECTION 2.1

2.1-1 Landfill Location Standards	2.1-4
---	-------

SECTION 2.2

2.2-1 Average Monthly Extremes and Precipitation for Kenosha, Wisconsin (1971-200)	2.2-6
2.2-2 Summary of Boring and Monitoring Well/Piezometer Information Within or Near the Proposed Vertical and Horizontal Expansion Area	2.2-35
2.2-3 Summary of New Piezometer and Monitoring Well Information	2.2-38

SECTION 2.3

2.3-1 Factors of Safety for Veolia ES Zion Landfill Site 2 East Expansion	2.3-7
2.3-2 Approximate Phasing of Cell Development	2.3-15
2.3-3 Typical Composition of Landfill Gas	2.3-21

SECTION 2.4

2.4-1 Storm Frequencies and Volumes	2.4-5
2.4-2 Design Parameters for Proposed Terrace Berms	2.4-7
2.4-3 Design Parameters for Proposed Downslope Flume Pipes	2.4-9
2.4-4 Design Parameters for Proposed Perimeter Ditches	2.4-10
2.4-5 Design Parameters for Proposed Culverts	2.4-11
2.4-6 Basin Design Parameters	2.4-12
2.4-7 Design Parameters for Proposed Detention Basin Outlet Structures	2.4-12
2.4-8 (a) Discharge for the 1-Hour Storm Events (CFS)	2.4-16
2.4-8 (b) Discharge for the 24-Hour Storm Event	2.4-18
2.4-9 Stormwater Detention Basin Design Hydrologic Results	2.4-21
2.4-10 Discharge Rates from Proposed Hydraulically Disturbed Areas to Regional Watersheds	2.4-22
2.4-11 Comparison of Existing to Proposed Discharge to Regional Watersheds from Proposed Hydraulically Disturbed Areas	2.4-22

SECTION 2.5

2.5 -1 60 Mil Smooth HDPE Geomembrane Acceptance Specifications	2.5.20-2
2.5 -2 60 Mil Textured HDPE Geomembrane Acceptance Specifications	2.5.20-3
2.5 -3 60 Mil HDPE Geomembrane Seam Testing Summary	2.5.20-4
2.5 -4 40 Mil Smooth LLDPE Geomembrane Acceptance Specifications	2.5.20-5
2.5 -5 40 Mil Textured LLDPE Geomembrane Acceptance Specifications	2.5.20-6
2.5 -6 40 Mil LLDPE Geomembrane Seam Testing Summary	2.5.20-7
2.5 -7 Geotextile Tests and Test Methods	2.5.20-8



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION TABLE OF CONTENTS

2.5 -8 6 Oz/Yd ² Geotextile Acceptance Specifications	2.5.20-9
2.5 -9 8 Oz/Yd ² Geotextile Acceptance Specifications	2.5.20-10
2.5 -10 Geonet Properties	2.5.20-11
2.5 -11 Geocomposite Properties	2.5.20-12
SECTION 2.7	
2.7-1 POLLUTE Model Parameter Values Site 2 East Expansion	2.7-8
2.7-2 Comparison of Model Predicted Results for the Shallow Drift Aquifer	2.7-13
SECTION 2.8	
2.8-1 Proposed Groundwater Monitoring Well Network Phasing	2.8-3
2.8-2 Existing and Proposed Leachate Sampling Points	2.8-20
SECTION 2.9	
2.9-1 Estimated Time Required for Closure (Months)	2.9-7
2.9-2 Premature Closure Cost Estimate	2.9-14
2.9-3 Post-Closure Care Cost Estimate	2.9-15
2.9-4 Summary of Required Financial Assurance	2.9-16
SECTION 3.1	
3.1-1 Land Use Percentages Within the One-Mile Study Area	3.1-6
3.1-2 Zoning Classifications Adjacent to and Surrounding the Facility	3.1-12
SECTION 3.2	
3.2-1 Population and Housing Data for Areas Surrounding the Subject Site	3.2-10
3.2-2 Income and Housing Construction Data for Areas Surrounding the Subject Site	3.2-11
3.2-3 Nearby Residential Subdivision Analysis	3.2-17
SECTION 6.1	
6.1-1 Percentage of Facility-Generated Traffic Volumes at Various Intersections	6.1-6
6.1-2 24-Hour Classification Traffic Counts	6.1-10
6.1-3 Approximate Truck Dimensions	6.1-12
6.1-4 Site Traffic Directional Distribution	6.1-14
6.1-5 Estimated Site-Generated Traffic Volumes	6.1-16
6.1-6 Level of Service Criteria: Unsignalized Intersections	6.1-23
6.1-7 Level of Service Criteria: Signalized Intersections	6.1-23
6.1-8 Intersection Level of Service and Vehicular Delay	6.1-24
6.1-9 Gap Distribution by Size and Type: Green Bay Road and Ninth Street	6.1-29
6.1-10 Gap Distribution by Size and Type: Green Bay Road and the Facility Access Drive	6.1-30
6.1-11 Green Bay Road at Ninth Street: Gap Supply and Demand	6.1-30
6.1-12 Green Bay Road at the Facility Access Drive: Gap Supply and Demand	6.1-31
SECTION 8.0	
8.0-1 Timeline of Solid Waste Planning in Lake County	8.0-6



**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

PHOTOGRAPHS

SECTION 2.2

2.2-1 Finished Piezometer/Monitoring Well	2.2-39
2.2-2 Typical Wadsworth Formation Sample Obtained with Split-Spoon Sampler	2.2-44
2.2-3 Typical Lower Till Sample Obtained with Split-Spoon Sampler	2.2-47

DIAGRAMS

SECTION 2.2

2.2-1 Simplified Diagram of Slug Test Assembly	2.2-41
--	--------

**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

GEOLOGIC DRAWINGS

G1	Title Sheet
G2	Private Water Well Location Map
G3	Boring Location Map
G4	Existing Monitoring Well, Piezometer, and Landfill Gas Probe Location Map
G5	Existing Groundwater, Landfill Gas, and Leachate Monitoring Network
G6	Geological Cross Section A – A'
G7	Geological Cross Section B – B'
G8	Geological Cross Section C – C'
G9	Geological Cross Section D – D'
G10	Geological Cross Section E – E'
G11	Geological Cross Section F – F'
G12	Geological Cross Section G – G'
G13	1995 Exiting Facility Geological Cross Section (C – C')
G14	1995 Exiting Facility Geological Cross Section (D – D')
G15	1995 Exiting Facility Geological Cross Section (E – E')
G16	1995 Exiting Facility Geological Cross Section (F – F')
G17	1995 Exiting Facility Geological Cross Section (G – G')
G18	1995 Exiting Facility Geological Cross Section (H – H')
G19	1995 Exiting Facility Geological Cross Section (Q – Q', R – R', S – S', and T – T')
G20	Top Elevation of the Wadsworth Formation
G21	Isopach of the Wadsworth Formation
G22	Top Elevation of the Shallow Drift
G23	Mass Excavation Grades
G24	Thickness of the Wadsworth Formation Below the Excavation
G25	Potentiometric Map of the Shallow Drift Aquifer – July 2007
G26	Potentiometric Map of the Shallow Drift Aquifer – October 2007
G27	Potentiometric Map of the Shallow Drift Aquifer – January 2008
G28	Potentiometric Map of the Shallow Drift Aquifer – April 2008

**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

DESIGN DRAWINGS

D1	Title Sheet
D2	Regional Facility Location
D3	Existing Facility Topography
D4	Excavation Grades
D5	Liner Grades
D6	Conceptual Geomembrane Panel Layout
D7	Leachate Collection System Overlain on Liner Grades
D8	Liner/Leachate Collection Details – 1
D9	Liner Leachate Collection Details – 2
D10	Existing Permitted Site 2 Final Landform
D11	Proposed Final Waste Grades
D12	Proposed Final Landform
D13	Cover/Monitoring Details
D14	Conceptual Landfill Gas Management System
D15	Landfill Gas Management System Details
D16	Stormwater Management System
D17	Stormwater Management System Details – 1
D18	Stormwater Management System Details – 2
D19	Typical Erosion Control Details
D20	Landfill Cross Section A – A'
D21	Landfill Cross Section B – B'
D22	Proposed Environmental Monitoring Plan

**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

LIST OF APPENDICES

Appendix A - Siting Application to City of Zion

A.1 - Application Fee

A.2 - City of Zion Pollution Control Siting Standards and Procedure

Appendix B - Pre-Filing Notices

Appendix C - Host Agreements

C.1 - City of Zion

C.2 - SWALCO/Lake County

C.3 - Village of Winthrop Harbor

C.4 - Zion Park District

Appendix D - Legal Descriptions

D.1 - Property Boundary Plat and Legal Description

D.2 - Proposed Facility Boundary Plat and Legal Description

D.3 - Expanded Site 2 Waste Boundary Plat and Legal Description

Appendix E - Need Report Data and Calculations

E.1 - Facility Life Calculations

E.2 - Waste Projections

E.3 - Waste Disposal Rates

E.4 - Remaining Capacity at Landfills Included in Needs Analysis

E.5 - Sample Calculations

Appendix F - Location Standards

F.1 - Airports

F.2 - Floodplain

F.3 - Wetlands

F.4 - Seismic Impact Zone

F.5 - Wild and Scenic Rivers

F.6 - Historic and Natural Areas

F.7 - Endangered Species

F.8 - Sole-Source Aquifer/Regulated Recharge Area

Appendix G - Hydrogeologic Investigation

G.1 - Climate Data

G.2 - Regional Water Well Logs

G.3 - USCS Classification Chart, Borng Logs, and As-Built Diagrams

G.4 - IDPH Well Construction and Abandonment Forms

G.5 - Groundwater Elevation Summary Table

G.6 - Horizontal and Vertical Gradient Summary Tables

G.7 - Monitoring Well/Piezometer Development Forms

G.8 - Horizontal Velocity Calculation for Shallow Drift Aquifer

Appendix H - In-Situ Hydraulic Conductivity Test Data

H.1 - Slug Test Summary (Most Recent Investigation)

H.2 - Slug Test Data (Most Recent Investigation)

H.3 - Slug Test Summary (Previous Hydrogeologic Investigation)



VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION TABLE OF CONTENTS

Appendix I - Laboratory Geotechnical Data

- I.1 - Laboratory Data Summary Tables (Most Recent Investigation)
- I.2 - Laboratory Data (Most Recent Investigation)
- I.3 - Laboratory Data Summary Tables (Previous Hydrogeologic Investigations)

Appendix J - Geotechnical Analyses

- J.1 - Summary of Geotechnical Design Parameters
- J.2 - Slope Stability Analysis
- J.3 - Stability of Liner and Leachate Collection System
- J.4 - Final Cover Geocomposite Drainage
- J.5 - Stability of Final Cover
- J.6 - Toe Drain Capacity
- J.7 - Anchor Trench Runout
- J.8 - Foundation and Waste Settlement
- J.9 - Bearing Capacity of Landfill Foundation
- J.10 - Final Cover Geomembrane Strain
- J.11 - Wheel Loading on Geomembrane
- J.12 - Wind Uplift on Geomembrane
- J.13 - Puncture Resistance of Geosynthetics

Appendix K - Leachate Collection System

- K.1 - Leachate Design Compatibility
- K.2 - Groundwater Seepage
- K.3 - Leachate Head
- K.4 - Leachate Storage Tank(s)
- K.5 - Laminar Flow in the Leachate Collection System
- K.6 - Capacity of Leachate Collection System Piping
- K.7 - Earthloads on the Leachate Collection System
- K.8 - Structural Capacity of the Leachate Collection Pipe
- K.9 - Ring Deflection of Leachate Collection Pipe
- K.10 - Leachate Treatment Permits
- K.11 - HELP Model

Appendix L - INTENTIONALLY LEFT BLANK

Appendix M - Stormwater Management

- M.1 - Determination of Rainfall Totals and Distributions
- M.2 - Watershed Delineation
- M.3 - Determination of Curve Numbers
- M.4 - Determination of SCS Lag Time
- M.5 - Orifice Discharge Calculations
- M.6 - Determination of Required Detention Volume
- M.7 - Live and Dead Storage Volume
- M.8 - Determination of Detention Basin Sediment Storage Evaluation
- M.9 - HEC-HMS Model Analyses
- M.10 - Ditch Size
- M.11 - Downslope Pipe Size
- M.12 - Culvert Size
- M.13 - Dissipator Structure Size
- M.14 - Emergency Spillway Size



**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

M.15 - Maintain Stormwater Volume to Isolated Waters of Lake County
M.16 - Drain tile survey
M.17 - Stormwater Pollution Prevention Plan
M.18 - SMC Technical Approval Correspondence
M.19 - Existing Watershed Development Permit
M.20 - Lake County Watershed Development Ordinance
M.21 - Existing NPDES Permit
M.22 - Zion Sanitary Landfill Watershed Development Permit Application (1998)
M.23 - Drawings Submitted to Lake County Stormwater Management Commission
for Pending Watershed Development Permit

Appendix N - Quantities

N.1 - Waste Volume Calculations
N.2 - Soil Quantity Calculations

Appendix O - INTENTIONALLY LEFT BLANK

Appendix P - Groundwater Impact Evaluation

P.1 - Model Documentation
P.2 - Baseline Model
P.3 - Sensitivity Analyses

Appendix Q - Environmental Monitoring

Q.1 - MEMO Model Output Files
Q.2 - Permitted AGQS Values
Q.3 - Typical Well Construction and Abandonment Forms
Q.4 - Sampling Procedures
Q.5 - Groundwater Sample Lists G1 and G2
Q.6 - Leachate Sample Lists L1, L2, and L3

Appendix R - Landfill Operations

R.1 - Spill Prevention Control and Countermeasure (SPCC) Plan
R.2 - Odor Control Plan
R.3 - Landfill Operator Certification

Appendix S - INTENTIONALLY LEFT BLANK

Appendix T - Health and Safety Programs

T.1 - Emergency Preparedness Program
T.2 - Veolia Health and Safety Policies
T.3 - Emergency Coordination Agreement with Zion Fire Department

Appendix U - Traffic

U.1 - Traffic Counts
U.2 - Capacity Analyses
U.3 - IDOT Accident Data
U.4 - Gap Study



**VEOLIA E.S. ZION LANDFILL - SITE 2 EAST EXPANSION
TABLE OF CONTENTS**

Appendix V - Company Information

V.1 - Applicant, Owner and Operator of Proposed Site 2 East Facility

V.2 - Articles of Incorporation

V.3 - Commitment to Obtain Insurance for Proposed Site 2 East Facility

V.4 - Veolia E.S. Solid Waste, Inc. Subsidiaries Operating or Licensed in Illinois in the
Field of Solid or Hazardous Waste Management

V.5 - List of Actual or Alleged Violations from the Last 10 Years of Veolia E.S. Zion
Landfill, Inc. and Veolia E.S. Solid Waste, Inc.

Appendix W - Resumes

